


# Perspectives from the US ITER Project

**Ned R. Sauthoff**

*Director, US ITER Project Office*

*NAS Committee for a Strategic Plan  
for U.S. Burning Plasma Research*

*August 29, 2017*



# Outline

---

- **Developments Since 2004**
  - Negotiations Phase
  - International Construction and Hardware Progress
  - ITER Management Turnaround
  - Hardware Progress in US
  - US Project Management
- **Project Engagements and Impacts**
- **Summary**
- **Further Information**





# Developments Since 2004


# Excerpts from NRC 2004 Recommendations

- “The United States should participate in a burning plasma experiment.”
- “The United States should participate in the International Thermonuclear Experimental Reactor (ITER) project. If an international agreement to build ITER is reached, fulfilling the U.S. commitment should be the top priority in a balanced U.S. fusion science program.”
- “The United States should pursue an appropriate level of involvement in the ITER project, which at a minimum would guarantee access to all data from ITER, the right to propose and carry out experiments, and a role in producing the high-technology components of the facility consistent with the size of the U.S. contribution to the program.”
- “A strategically balanced U.S. fusion program should be developed that includes U.S. participation in ITER, a strong domestic fusion science and technology portfolio, an integrated theory and simulation program, and support for plasma science. As the ITER project develops, a substantial augmentation in fusion science program funding will be required in addition to the direct financial commitment to ITER construction.”


Source: National Research Council. 2004. *Burning Plasma: Bringing a Star to Earth*. Washington, DC: The National Academies Press. <https://doi.org/10.17226/10816>, p. 4, 6.




# Project History



# High Level International Procurement Arrangements



# High Level US Procurement Arrangements





An aerial photograph of a massive construction site, likely for a large-scale infrastructure project. The scene is dominated by a large, circular concrete structure under construction in the lower-left quadrant, surrounded by a dense network of steel reinforcement and scaffolding. To its right, a long, rectangular building frame is visible, also under construction. In the upper-left, a large, dark-colored building with a curved facade is partially completed, featuring a large yellow and white graphic on its side. Two prominent red and white tower cranes stand tall against the clear blue sky, their jibs extending over the construction area. The background shows a green, hilly landscape under a bright blue sky. The overall scene conveys a sense of large-scale industrial activity and engineering progress.

# International Construction



**Radio Frequency Bldg.**

Hosts the radio wave-generating systems that will contribute to heating the plasma.

**Assembly Hall**

Components will be pre-assembled in this 6,000-square-meter building, equipped with a double overhead traveling crane and powerful handling tools.

**Poloidal Field Coils Winding Facility**


Four of the six poloidal field coils will be produced by Europe in this 257-meter long facility.

**Cryoplant**

Will provide coolant to the Magnet Systems, the cryopumps and the thermal shield.

**400 kV Switchyard**

Connects the site to the grid.

**Service Bldg.**

Accommodates a large number of industrial support services and systems.

**Tritium Bldg.**

Houses tritium systems.

**Tokamak Bldg.**

The crane C1, near the center of the bioshield, marks the approximate axis of the ITER Tokamak.

**Diagnostics Bldg.**


Houses the electronic and information systems that will receive, record and interpret signals from the operational arena.

**Magnet Power Conversion Bldgs.**

Host the AC/DC converters that feed power to the magnets.





## 10






# Tokamak Complex





# Assembly Building, Cleaning Facility and RF Heating Building






# Assembly Building






# RF Heating Building





# Poloidal Field Coils Winding Facility and Cryoplant





# Poloidal Field Coils Winding Facility





# Cryoplant Building





# Cryostat Workshop






# Cryostat Workshop






# Magnet Power Conversion Buildings





# Switchyard






A photograph of a construction site under a clear blue sky. In the foreground, a row of flagpoles holds the flags of the United States, Russia, South Korea, Japan, India, the European Union, and China. Behind the flags, a large building is under construction, with a yellow banner that reads "BRINGING THE POWER OF THE SUN TO EARTH" and the ITER logo. A large crane is visible in the background.

# Hardware Progress in Domestic Agencies



# Toroidal Field Conductor


*Korea*




*Russia*



*China*




*Japan*



*EU*



*United States*



**All toroidal field conductor has been delivered**



# EU Progress



A poloidal segment of one vacuum vessel sector is fitted. Four segments, each weighing over 6 tonnes, form the full sector.  
Photo: Walter Tosto



Production winding has begun for poloidal field #5. Photo: ITER Organization

**Scope: Buildings, Vacuum Vessel, Magnet Systems, Power Systems, Heating & Current Drive Systems, Cryoplat, Divertor, Fuel Cycle, Blanket, Tritium Plant, Diagnostics, Radioactive Materials**





# Korea Progress



Port stub assembly for Sector 6 of the vacuum vessel.

Photo: ITER Korea



The first fully assembled, 800-tonne vacuum vessel sector sub-assembly tool (SSAT) has been test fitted and is ready to ship to the ITER site.

The first batch of elements arrived in June.

Photo: ITER Korea

**Scope: Vacuum Vessel, Thermal Shield, Magnet Systems, Assembly Tooling, Power Systems, Blanket, Tritium Plant, Diagnostics**





# India Progress



The lower cylinder of the cryostat is now being assembled in the Cryostat Workshop at the ITER site. Photo: ITER Organization



Thousands of in-wall shielding plates have been fabricated at Avasarala Technologies Ltd. in Bengaluru, Karnataka. Deliveries to Korea began in 2015. Photo: ITER India

**Scope: Vacuum Vessel, Cryostat, Cryogenic Systems, Heating and Current Drive Systems, Cooling Water System, Diagnostics**





# Russian Federation Progress



This port stub extension component has successfully passed pressure and helium leak tests in accordance with French regulations on pressure equipment (ESPN). Photo: ITER Russia



At the Efremov Institute in Saint Petersburg, equipment for ITER's switching network and fast discharge units has been fabricated and over 70 tonnes of material, including aluminum busbars and busbar components, was shipped in December. Photo: ITER Russia

**Scope: Vacuum Vessel, Magnet Systems, Power Systems, Blanket, Divertor, Diagnostics, Heating & Current Drive Systems**



# Japan Progress



Japan completed its first toroidal field winding pack in January. Photo: ITER Japan




The 1 MV bushing at Hitachi for the full-scale ITER neutral beam injector. The bushing has since been delivered to the PRIMA neutral beam test facility in Italy for the MITICA (Megavolt ITER Injector and Concept Advancement) test bed. Photo: ITER Japan

**Scope: Magnet Systems, Heating & Current Drive Systems, Remote Handling, Divertor, Tritium Plant, Diagnostics**





# China Progress



Qualification activities for ITER's smallest poloidal field magnet (PF6) are underway at ASIPP in Hefei, China. A dummy double pancake winding was completed in January 2017 and successfully passed a manufacturing readiness review. Photo: ITER China



A prototype side correction coil (SCC) at ASIPP is made of eight layers of niobium-titanium superconductor. Photo: ITER China

**Scope: Magnet Systems, Power Systems, Blanket, Fuel Cycle, Diagnostics**





# ITER Management Turnaround



# 2015-2017 Timeline

**March 2015:** Director General Bernard Bigot appointed and action plan approved by ITER Council.

**November 2015:** Resource-loaded “Overall Project Schedule to 1st Plasma” presented to ITER Council, including 29 milestones for 2016-2017.

**April 2016:** Independent ITER Council Review Group finds that sequence and duration of resource-loaded schedule are logical, and inventory and integration of schedule activities are complete.

**June 2016:** Construction-Management-as-Agent contract signed with MOMENTUM joint venture, to manage and coordinate assembly and installation of Tokamak and associated plant systems.

**November 2016:** ITER Council approves\* Overall Project Schedule through 1st Plasma in 2025 and onward to start of Deuterium-Tritium (DT) operation.

\*Subject to Members' internal approval processes.



# ITER Management has been Significantly Improved

---

- **Project decision-making more effective**
  - Executive Project Board
- **Risk/issue management upgraded, and mitigation actions taken**
  - Vacuum Vessel segments transferred from EU to IO to Hyundai Heavy Industry
  - Building services installation scope transfer from EU to IO...
- **Systems engineering and configuration management improved**
  - Central integration and systems engineering: systems, training and utilization
  - Interface resolution and control
- **Project controls upgraded**
  - Greatly improved project management and team-building/ training
  - Milestones established and achieved



# All 25 IC Milestones

## Due by the End of Q2 2017 Achieved

2016Q1: Tier-1 Cryostat Base Section Delivered

2016Q1: B1 Civil Works Started in Tokamak Bldg.

2016Q1: Lot-1 Piping Delivered

2016Q1: IC Independent Reviews Initiated

2016Q2: Assembly Hall Main Cranes Erected

2016Q2: 1st EU TF Winding Pack Completed

2016Q2: TF Conductor Fabrication from RF, CN  
and JA Completed

2016Q2: PF5/2 Conductor Fabrication Completed

2016Q2: Divertor OVT Unit Test Completed

2016Q2: WDS Tanks Installed in Tritium Bldg.

2016Q2: CS Module 1 Winding Completed

2016Q2: 1st Independent Review Report  
Completed

2016Q3: CMA Contract Signed

2016Q3: 4th US TF Conductor Unit Length Completed

2016Q3: IC-Agreed Staffing Positions Recruited

2016Q4: 1st Vacuum Vessel Sub-segment Completed

2016Q4: 1st LN2 Refrigerator FAT Completed

2016Q4: SSEN Power Transformers Delivered

2016Q4: LHe Plant Equipment FAT Completed

2016Q4: VAS Flanges Ready to Ship

2017Q1: 1st JA TF Winding Pack Completed

2017Q1: 400 kV Switchyard Energized

2017Q2: Start of Work Cryopant Compressor Bldg. 51

2017Q2: Completion of RFE 1A (Assembly Hall)

2017Q2: Receiving Inspection of Sector Sub-Assembly  
Tool (SSAT)






# Hardware Progress in the US





# US ITER Hardware Scope

## Full Scope





# ITER Project has Defined First-Plasma and Post-First-Plasma Hardware




← **US First Plasma SP-1** →

← **US Post-First Plasma SP-2** →

R&D and Design	Full Fabrication	Partial Fabrication	Completion of Fabrication	Full Fabrication
Completion for All Hardware	<ul style="list-style-type: none"> <li>• Central Solenoid (in fabrication)</li> <li>• Toroidal Field Conductor (completed in FY17)</li> <li>• Steady State Electrical Network (to be completed in FY17)</li> </ul>	<ul style="list-style-type: none"> <li>• Tokamak Cooling Water System (some delivered)</li> <li>• Roughing Pumps</li> <li>• Vacuum Auxiliary System (some delivered)</li> <li>• Pellet Injection</li> <li>• Ion Cyclotron Heating</li> <li>• Electron Cyclotron Heating</li> <li>• Diagnostics</li> <li>• Instrumentation &amp; Controls</li> </ul>		<ul style="list-style-type: none"> <li>• Tokamak Exhaust Processing</li> <li>• Disruption Mitigation</li> </ul>



# US SP-1 Systems by Value



\*Includes CS Modules, Structures & Assembly Tooling

Data: June 2017



# Toroidal Field Conductor Completed



Strand was produced by Luvata Waterbury, Inc. in Waterbury, CT (above) and Oxford Superconducting Technologies in Carteret, NJ.



Cabling of the strand was performed by New England Wire Technologies in Lisbon, NH.



The conductor was jacketed and integrated at High Performance Magnetics in Tallahassee, FL and Criotec in Chivasso, Italy (above).



# Steady State Electrical Network Nearly Complete (will finish in FY17)



The final shipments of power transformers were delivered in December 2016.



The first lots of reactive power compensators were shipped in April 2017; the remainder will be shipped by September.



Reactive power compensators in final assembly testing before shipment.



HV transformers were delivered and installed on site in 2015.



# Central Solenoid Module Fabrication Progressing





General Atomics developed a 64,000 ft<sup>2</sup> Magnet Technologies Production facility with 10 work stations



# US Hardware

## Central Solenoid Module Fabrication Progressing



Left: Winding of Modules #1 and #2 is complete; #3 is underway. Middle: Heat treatment of the Module #1 is complete. Right: Module #1 is now in the turn insulation station. Photos: GA



# Tokamak Cooling Water System

Initial deliveries complete; piping fabrication underway

Final Design Review for First Plasma hardware planned for November 2017



Drain tanks fabricated in the US were the first nuclear-certified components delivered to the ITER site (September 2015).




Pipe fabrication is underway at the Schulz Xtruded Products facility in Robinsonville, MS.



# US Hardware

## Vacuum Auxiliary System

Deliveries in Progress; prototypes in testing



Tokamak vacuum volume: 1330 m<sup>3</sup>  
Cryostat vacuum volume: 8500 m<sup>3</sup>  
Neutral beam injector volume: 860 m<sup>3</sup>  
Vacuum system performance: 105 Pa → 10 Pa in 24 hours  
Vacuum operating pressure: 1 x 10<sup>-4</sup> Pa  
Roughing pumps: 400+ vacuum pumps  
(10 different technologies)  
Service vacuum system: >1500 clients  
Vacuum piping: 6 km




Hydrogen Isotope  
Selective Pumping Unit (HISPU)



# US Hardware

## Vacuum Roughing Pumps

- Novel second stage pumps regenerated hydrogen isotopes fuel and helium from first stage cryo-sorption pumps.
- Hydrogen isotopes pumped by cryo-condensation and helium pumped by the flow of hydrogen isotopes and mechanical pumps
- Separates fuel and helium created in the fusion process.






# US Hardware


## Ion Cyclotron Transmission Lines

Prototypes in fabrication and testing; production unit fabrication started

- 20 megawatts total power transfer to the plasma
- Up to 6 megawatts per line



Tri-axial vibrational test stand



Insulator flange with 3-spoke quartz pin supports




# Electron Cyclotron Transmission Lines

Prototypes in fabrication and testing; contracts for manufacturing processes awarded

- 20 megawatt total power transfer to the plasma
- 1.2 megawatts per line



A laser-based wave guide inspection system was developed




1.5 MW power load test stand




# Pellet Injection and Disruption Mitigation Systems

- Prototypes are in fabrication and testing; testing on current tokamaks continues
- Cryogenic pellet plasma fueling in development to perform at 300 m/s at 16 Hz



A shattered 7 mm neon pellet in DIII-D tokamak plasma




A three-barrel prototype for shattered pellet injection (SPI). SPI components will be installed on JET for further testing.



# US Hardware Diagnostics

State of the art distributed plasma diagnostics are in design, with prototypes in fabrication and testing







# Tokamak Exhaust Processing

## Design activities continue

- High-throughput ( $240 \text{ Pa}\cdot\text{m}^3/\text{sec}$ ) tritium processing system is in design.
- Palladium membrane separates hydrogen isotopes from methane-steam reforming reaction



High density of equipment in Tritium Building



Typical glovebox





# U.S. Project Management



# Assessment of US Performance

---

## **June 2014, GAO:**

- *US ITER Project's schedule "fully reflects the characteristics of high-quality, reliable schedule estimates"*
- *US ITER's cost estimate "substantially met best practices for comprehensive, well documented, and accurate estimates"*

## **April 2015, DOE audit of US ITER QA Program:**

- *".... Rigorous process controls for integration of quality principles in all aspects of procurement, design, fabrication and inspection/acceptance testing"*

## **April 2015, DOE Office of Project Assessment**

- *"capable management team, and the processes and tools are in place to deliver on the near-term scope"*




# Robust Risk Management System Utilized Since 2006

## June 2013, DOE Independent External Review Committee:

*"The review team found that the US ITER project has developed a relevant and comprehensive risk analysis with a state-of-the-practice process for developing contingency as well as a reasonable and comprehensive approach to risk identification."*

### Reports/Results (Primavera Risk Analysis)





# DOE Deputy Secretary Approved First Plasma Performance Baseline and Total Project Range on January 13, 2017

## DOE-approved Package (Jan 2017)

### First Plasma Project Baseline (CD-2/3):


- Total project cost (TPC): \$2.5B
- CD-4: December 2027

### Total US ITER Project Range (CD-1R):

- Cost range: \$4.7B–\$6.5B
- CD-4: 2034–2038

*driven by budgetary constraints—not technical*

**September 2034 – March 2038**






# 16% of All US Hardware Has Been Delivered

- Deliveries by the US of early-need hardware began in 2013
- Deliveries have continued on-pace with the evolving international schedule

**US Hardware Deliveries**





# Project Engagements and Impacts



# Industries are Engaged

Industry	Area of Contribution
<b>General Atomics</b> , San Diego, CA	Central Solenoid modules
<b>AREVA Federal Services, LLC</b> , Charlotte, NC	Tokamak Cooling Water System design and drain tank fabrication
<b>Luvata Waterbury, Inc.</b> , Waterbury, CT	Toroidal Field conductor strand
<b>Precision Custom Components</b> , York, PA	Central Solenoid lower structures and tie plates
<b>Transproject</b> , Houston, TX	Shipping
<b>Oxford Superconducting Technology</b> , Carteret, NJ	Toroidal Field conductor strand
<b>High Performance Magnetics</b> , Tallahassee, FL	Toroidal Field conductor integration/jacketing
<b>Schneider Electric</b> , Palatine, IL	Steady State Electrical Network components
<b>Robatel Technologies</b> , Roanoke, VA	Central Solenoid assembly tooling
<b>Petersen, Inc.</b> , Ogden, UT	Central Solenoid structures
<b>Superbolt</b> , Carnegie, PA	Central Solenoid tensioning components
<b>Hyundai Corporation</b> , Houston, TX	Steady State Electrical Network HV transformers
<b>New England Wire Technologies</b> , Lisbon, NH	Toroidal Field cabling
<b>Robatel Technologies LLC</b> , Roanoke, VA	Central Solenoid assembly tooling
<b>Hamill Manufacturing</b> , Trafford, PA	Central Solenoid upper structures
<b>Major Tool &amp; Machine, Inc.</b> , Indianapolis, IN	Central Solenoid structure R&D
<b>Mega Industries, LLC</b> , Gorham, ME	Ion Cyclotron heating
<b>Dielectric Communications</b> , Raymond, ME	Ion Cyclotron heating
<b>Siemen's Industry, Inc.</b> , Wendall, NC	Steady State Electrical Network control & protection
<b>Eaton Corporation</b> , Cleveland, OH	Steady State Electrical Network switchgear
<b>G&amp;G Steel</b> , Russellville, AL	Central Solenoid structure tie plate prototype
<b>ABB</b> , Raleigh NC	Steady State Electrical Network transformers



# Universities are Engaged

University	Area of Contribution
Columbia University	Project support
Florida State University	Analysis for toroidal field strand and conductor, central solenoid conductor and tie plates
Indiana University	Core imaging x-ray spectrometer R&D
Massachusetts Institute of Technology	Electron cyclotron R&D, central solenoid analysis, quench detection
University of California Los Angeles	Computational fluids dynamic analysis, ITER team training
University of California San Diego	Magnet design review support
University of Michigan	ITER stainless steel
University of Tennessee	ITER stainless steel, central solenoid and toroidal field conductor R&D, central solenoid module R&D, radiation modeling
University of Texas at Austin	Electron cyclotron emission diagnostic R&D
University of Wisconsin at Madison	Global neutronics
Washington State University	Pellet injector experimental support



# National Laboratories are Engaged


National Laboratory	Area of Contribution
Oak Ridge National Laboratory	Overall U.S. project management, systems engineering, fuel pellet injection technology, and high-performance computing for theoretical models
Princeton Plasma Physics Laboratory	Advanced microwave, laser, x-ray and optical diagnostic instruments, and theoretical models
Savannah River National Laboratory	Exhaust gas processing and tritium recovery
Argonne National Laboratory	Neutronics analysis
Fermi National Accelerator Laboratory	Solenoid cold testing and toroidal field strand testing
Idaho National Laboratory	Beryllium dust characteristics, codes and standards
Lawrence Berkeley National Laboratory	Solenoid support structure design
Lawrence Livermore National Laboratory	Magnet systems design and analysis
Los Alamos National Laboratory	Tritium plant R&D and massive gas injection
Sandia National Laboratory	Blanket and shield R&D and design



# Over 80% of Awards and Obligations Remain in the US


600+ contracts awarded to US industry and universities, and obligated to DOE national laboratories in 44 states

500+ direct jobs and 1100+ indirect jobs created or maintained per year.




Data as of June 30, 2017


# ITER Technologies Advance Domestic Capabilities and Capacities




**High Power  
Superconducting  
Cable-in-Conduit**  
7 kV @ 68kA




**High Power,  
High Purity  
Microwave Power  
Transmission**  
20 MW transfer capacity,  
1.2 MW/line  
> 90% mode purity




**High Field,  
High Storage  
Superconducting  
Magnets**  
5.5 GJ storage  
capacity  
13.1 T field



**High Power,  
Low Loss  
Radiofrequency  
Power Transmission**  
20 MW transfer capacity,  
6 MW/line




**High Velocity,  
High Rate  
Cryo-Pellet  
Injection**  
300 m/s second  
16 Hz



**Neutronics Modeling**  
75 million spatial tally cells  
10,000X reduction in  
computational time



# Summary



# ITER status summary

---

- ITER negotiations led to international agreement and ITER construction
- The ITER Organization is now well-managed and is integrating the project
- Construction and fabrication are well underway on
  - Buildings and plant infrastructure at the ITER site
  - Hardware components in all Domestic Agencies
- The US ITER Project has been baselined and has performed well
- US universities, industries and government institutions are engaged



# “the importance of U.S. research supporting ITER to the development of fusion energy”

- U.S. burning plasma research is already underway with existing facilities and modelling/simulation, positioning the U.S. to be among the BP-research leaders before and on ITER
  - Guides the design (e.g., disruptions and other transients)
  - Supports operations (e.g., plasma instrumentation and control, predictive models and analysis tools)
  - Enables leading research (e.g., advancing burning plasma understanding and creating related tools such as predictive models for designing BP experiments and interpreting BP data)
- ITER physics and hardware design, the ITPA, and Joint Experiments have
  - Achieved **global convergence** on priorities for advancing tokamak-based fusion science and fusion technology, focusing on issues for a real device
  - Been highly effective as a **forcing function** for progress in fusion science and technology

# **“the scientific and technical developments since the 2004 report of the NAS Burning Plasma Assessment Committee”**

---

- Physics developments have supported ITER design and research planning
  - Cf. Tony Taylor’s presentation
- Technology developments have enabled the design of ITER’s high-tech systems
  - Cf. Phil Ferguson’s presentation
- Research since 2004 has strengthened our confidence in ITER performance



# Possible statements for the Committee

- Tokamaks remain the only concept mature enough to now serve as the basis for a near-term burning plasma experiment.
- The ITER Project, the International Tokamak Physics Activity, and Joint Experiments have
  - Achieved **global convergence** on priorities for advancing tokamak-based fusion science and fusion technology, focusing on issues for a real device; and
  - Been highly effective as a **forcing function** for progress in fusion science and technology.
- Research since the NAS Burning Plasma Report (2004) has strengthened our confidence in ITER performance.



## Further Information

[2016 ITER Organization Annual Report](#)